

## Economics of Nuclear Power from Heavy Water Reactors

*Using a discounted cash flow methodology, this paper performs a detailed analysis of the current costs of electricity from two of the Department of Atomic Energy's heavy water reactors. It compares these costs to that from a recently constructed coal-based thermal power plant. The cost so computed is a sensitive function of the discount rate (a measure of the value of capital) used and the results show that for realistic values of the discount rate, electricity from coal-based thermal power stations is cheaper than nuclear energy.* **M V RAMANA, ANTONETTE D'SA, AMULYA K N REDDY**

The Department of Atomic Energy (DAE) has been promoting nuclear power as the "obvious choice for India to solve its energy problems in the long-term" [Bhoje 2001]. Such promises that nuclear power would play an important role in satisfying India's energy needs have been routinely offered since the 1950s, but the actual growth of nuclear power in the country has been extremely modest. As of January 2005, the total installed nuclear power generation capacity is 2,770 MW, less than 3 per cent of the total installed electricity generation capacity in the country.<sup>1</sup>

The promise offered by DAE is not only that nuclear power would form an important component of India's electricity supply, but that it would be cheap. As early as 1958, barely a few years after the DAE was set up, Homi Bhabha, the chief architect of the programme, projected "the contribution of atomic energy to the power production in India during the *next 10 to 15 years*" and concluded that "the costs of [nuclear] power [would] compare *very favourably* with the cost of power from conventional sources in many areas" (emphases added) [Bhabha and Prasad 1958]. The 'many areas' referred to regions that were remote from coalfields. In the 1980s the DAE stated that the cost of nuclear power "compares quite favourably with coal fired stations located 800 km away from the pithead and in the 1990s would be even cheaper than coal fired stations at pithead" [Srinivasan 1985b]. This projection was not fulfilled. A more recent Nuclear Power Corporation (NPC) internal study comes to the less optimistic conclusion that the "cost of nuclear electricity generation in India remains competitive with thermal [electricity] for plants located about 1,200 km away from coal pit head, when full credit is given to long-term operating cost especially in respect of fuel prices".<sup>2</sup>

Despite its inability to live up to its promises, the DAE has always received high levels of financial support from the government, which have increased over the last few years (Table I).<sup>3</sup> This government support has once again revived the hopes of the DAE for large-scale expansion; the DAE envisions having a total installed capacity of 20,000 MW of nuclear power by the year 2020 [Joseph 1999]. The largest component of this would be in the form of Pressurised Heavy Water Reactors (PHWR) [Chidambaram 2001].<sup>4</sup>

This anticipated increase in nuclear power capacity, in particular the focus on PHWRs, makes an assessment of the economics of electricity generation in these reactors particularly relevant and urgent. Over a decade ago, a comparison of energy technologies had concluded that other options like coal and hydroelectric power were cheaper than nuclear power under realistic assumptions and "even if the projections and scenarios indicate large demand-supply gaps in the future, the most expensive way of bridging these gaps is through nuclear power plants" [Reddy et al 1990].

The present study was undertaken with the hope that over the last decade more information on the expenditures actually incurred would have become publicly available, allowing a better and more reliable estimate of the costs of electricity generated in recently constructed and proposed reactors. This hope has been only partially realised. While the total expenditure on various reactors is available, details about operational and maintenance expenditure, the cost of producing heavy water, and so on, are not available in the public domain. Nevertheless, using the available current information, and making reasonable assumptions or extrapolations from other countries, we have calculated the 'busbar' cost of generating electricity (i.e., not including transmission and distribution costs) that is delivered to the grid (i.e., taking auxiliary or in-plant consumption of electricity into account).<sup>5</sup>

In order to assess the economics of nuclear power, one has to weigh these costs against the corresponding costs of generating power through some roughly comparable technology. For this purpose we follow the DAE's analyses and choose coal-based thermal power plants, which constitute 58 per cent of India's generation capacity [CEA 2003]. Like nuclear reactors, these provide base-load electricity.

### Methodology

The conventional accounting procedure adopted often by Indian energy planners is the return-on-investment (ROI) approach. Here the unit energy cost includes four components: return on (capital) investment, depreciation of capital, annual costs of fuel and other materials, and operational and maintenance costs. Though widely used, this approach has important shortcomings. In particular, it ignores the time value of money and the gestation period of the project. For example, the total capital cost of the project is calculated by adding up capital expenditure figures from various years.<sup>6</sup> This means that a project that takes many years to build and generate electricity would appear equivalent to one which delivers power in a shorter time but with the same total investment.

We therefore use the discounted cash flow (DCF) approach that is widely used in investment analysis [Brealey and Myers 2000]. This has been applied to earlier studies of the costs of nuclear power [Reddy et al 1990], but we have fine-tuned it for this study by taking into account many of the sub-processes involved in nuclear power production. The principle underlying this approach is that money received today is worth more than the same amount of money received later; for example, at an effective annual interest (or discount) rate of 10 per cent, today's one rupee would be equivalent to Rs 1.10 a year from now.<sup>7</sup> Therefore the timing of cash inflows and outflows is important. In the DCF approach, all costs are discounted to some arbitrary but fixed reference date; the total cost reckoned at this reference point is the sum of the present values (PV) or future values (FV) of costs discounted to this date. Similarly one can calculate the present value of the revenues from the expected sale of electricity from the project. The levelised cost of electricity is then determined by setting the sum of discounted costs equal to the sum of discounted revenues.

We will express all costs in 2002 (fixed year) rupees. Our results will therefore be in terms of real discount rates rather than nominal rates. However, the two are equivalent. To convert costs from one year to another, we use the ratio of GDP deflators for the respective years as specified by the World Bank.<sup>8</sup> These are listed for the last 22 years in Table 2.

The cost of generating electricity consists of three main components: the capital cost of constructing the generating facility, the annual fuelling and operations and maintenance (O&M) costs, which must be incurred as long as the facility is running, and the waste management expenses from the running of the facility in an environmentally acceptable manner. One other component in the case of nuclear power is that of decommissioning the reactors. Though this is an expensive process, because it is done only many years into the future, its discounted cost will be small. In mathematical terms:

$$PV(\text{costs}) = \sum_{l=-M}^0 C_l / (1+i)^l + \sum_{K=1}^N [(O_k + F_k) / (1+i)^k] + \sum_{J=P+1}^{N+P+1} W_j / (1+i)^j + \sum_{q=N}^{n+1} D_q / (1+i)^q$$

where  $C_j$  = capital cost in year 1;  $M$  = total number of years of construction before reactors becomes commercial;  $i$  = real discount rate;  $N$  = number of years of operation;  $O_k$  = operations

**Table 1: Government Outlay for DAE**  
(In crores of rupees)

	1997-1998	1998-1999	1999-2000	2000-2001	2001-2002	2002-2003	2003-2004	2004-2005	2005-2006
Budget estimate	1,836.53	2,608.06	2,962.01	2,750.57	2,779.39	3,868.95	3,800.09	4,469.97	4,995.86
Revised budget	1,996.33	2,418.12	2,682.04	2,745.21	2,768.59	3,351.69	3,738.77	4,240.46	

Source: Union Expenditure Budgets 1998 through 2005 (Plan + Non-plan expenditure).

**Table 2: GDP Deflator Data for India**  
(Base Year: 1993)

Year	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991
Deflator	36.1	38.9	42.3	45.5	48.7	52.0	56.8	61.6	66.7	73.7	83.9
Year	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002
Deflator	91.3	100.0	109.7	119.5	128.2	136.5	147.3	153.0	159.9	165.4	172.0

Source: The World Bank database (available on the Internet to subscribers).

and maintenance (O&M) cost in year k of operation;  $F_k$  = fuel cost in year k of operation; W: = waste disposal cost in year j; P = cooling time for spent fuel; D = decommissioning cost; T = number of years after completion of operations before decommissioning is expected to take place. Note that in the first term on the right hand side of the equation, all of the exponents in the denominator are non-positive since the index runs from -M to 0.

The present value of the revenue generated by selling electricity is given by

$$PV(\text{revenues}) = C_e \sum_{k=1} E_k / (1+i)^k$$

where  $C_e$  = levelised cost per kilowatt hour (kWh), and  $E_k$  = energy in kWh generated in year k.

When calculating the price of electricity from a power plant that is yet to be constructed, it is normal to assume that annual energy production is constant. It is also assumed that the O & M, fuel, and waste management costs will increase due to inflation, but are constant in real terms. Since we will be working in fixed year rupees, they will be constant in our calculations.

We will find that the results of our analysis depend sensitively on the discount rate used. There is no consensus on what this rate should be since it is an expression of how planners wish to allocate resources and how they value future benefits in comparison with current sacrifices. The Central Electric Authority has been using a 12 per cent discount rate in their calculations for planning and evaluation of projects [Bose 2000]. So has the Planning Commission. However, this is a nominal discount rate and translates to a real discount rate of about 6-7 per cent at the prevalent 5-6 per cent inflation rates. Our calculations will use a real discount rate, which we vary in order to test the results.

## Capital Costs

The largest component of the cost of producing electricity in the case of nuclear reactors is the capital cost of the reactor. Operating costs typically constitute only a small part of the cost of generating electricity in nuclear reactors. The capital cost consists of the construction cost, and the costs of the initial loading of fuel and heavy water. Within the DCF methodology, one does not include the interest during construction (IDC) that is often mentioned as part of the cost of reactors, since interest results from the need to borrow money and is not relevant when comparing alternative investments.<sup>9</sup> Inclusion of the interest component would make nuclear power projects more unattractive since they are capital intensive and take longer to construct; hence, this is a conservative assumption (i.e., favourable to nuclear power).

Capital costs can vary considerably. We consider two specific cases, one set of two reactors already commissioned, and another set being constructed.<sup>10</sup> In the first case, we use the actual costs of the two 220 MW reactors at Kaiga Nuclear Power Station (Kaiga I and II) that were commissioned in 1999. Along with the RAPS III and IV reactors, these are the newest reactors; thus, one expects that these would have incorporated the lessons of the DAE's experiences with earlier reactors and also be indicative of the future as far as similar reactors are concerned. In the second, we use the projected costs of the two 220 MW reactors at the same site (Kaiga III and IV) that are scheduled to be commissioned in December 2006 and 2007.

### *Construction Costs*

The initial cost estimate of Kaiga I and II, which were originally scheduled to be completed in 1994 [Srinivasan 1985a]; reprinted in [Srinivasan 1990:127-37], was Rs 730.72 crore [DAE 1996: 67]. However, these plants became critical only in 1999. At the time of criticality, the cost of the project was estimated at Rs 2,896 crore [DAE 1996: 67].<sup>12</sup> The yearwise expenditure on the project is given in Table 3. In our calculations, we convert the expenditure for each year to 2002 rupees using the ratio of GDP deflators in Table 2.

One reason for the long delay and cost-overrun in the case of the Kaiga I and II reactors was that the containment dome - the structure that is supposed to prevent the escape of radioactivity into the environment should an accident occur - of one of the units collapsed in May 1994.<sup>13</sup> But all the reactors built by the DAE have had cost overruns (Table 4).

A 1988 study by the Comptroller and Auditor General of India (CAG) of the Narora reactors listed 10 major heads of expenditure that had cost overruns of 188 per cent or more [CAG 1988]. The CAG concluded that the revision of costs by 95 per cent in 1982 and 64 per cent in 1985 indicates that the project got "approved on unrealistic cost estimates. Unrealistic cost estimates and optimistic time schedules make financial allocations and controls less meaningful." Cost increases, though not of such a large magnitude, have occurred with nuclear reactors in other countries as well.<sup>16</sup> There is, therefore, the strong likelihood that capital costs are likely to increase. Despite this, in order to be conservative, we will use the stated estimated costs for all upcoming reactors.

The financial sanction for Kaiga III and IV, the reactors being constructed at the same site as Kaiga I and II, is Rs 4,213 crore, including an interest during construction (IDC) component of Rs 534 crore, or about 12.7 per cent of the total [DAE 2002b: 94]. Later reports suggest that the NPC anticipates a shorter gestation time and has lowered the estimated cost to Rs 3,282 crore [Lal 2002]. The reduction of the estimated costs are due not only to lower gestation times but also due to a reduction in the prevailing rates of inflation and interest, and government concessions given to mega projects [DAE 2002a]. It is not clear how much of the estimated cost is IDC. In line with the earlier DAE (2002b) estimate, we will assume that IDC constitutes 12.7 per cent of the total cost, or Rs 416 crore.

Plant excavation work for these reactors started in March 2001 and they are scheduled to become critical in 2006 and 2007 respectively [NPC 2004a]. However, advance procurement for these reactors began as early as 1990-91 [DAE 1991: 1.4]. Up to March 2000, Rs 394.05 crore had been spent on the project [DAE 2002b: 94]. Once again, we assume that 12.7 per cent of this constitutes IDC. We also assume that the expenditure was uniform over these years. For the remaining period and amount we assume a different pattern of annual expenditure, shown in Table 5, anticipating shorter construction times. This follows the pattern of expenditure for Canadian PHWRs [NBA 1998: 60].

### **Heavy Water Inventory Costs**

Heavy Water (HW) reactors, as the name suggests, require heavy water - water with the hydrogen replaced by deuterium, a heavier isotope of hydrogen. The HW is used both as moderator (to slow down neutrons emitted during fission so that they have a higher probability of being captured by other fissile nuclei) and as coolant (to carry away the heat produced).

The initial coolant and moderator inventory requirements for each 220 MW PHWR are 70 and 140 tonnes of HW respectively [NEI 1994]. The NPC reportedly treats the initial HW requirements as a non-depreciating asset and calculates lease charges at 8 per cent per annum to be paid to the DAE [Muralidharan 1988]. Within the DCF methodology, the correct way to include the cost is to treat the initial HW inventory as an up-front capital cost.

**Table 3: Expenditure Pattern (without IDC) for Construction of Kaiga I and II**

Year	1983-84	1984-85	1985-86	1986-87	1987-88	1988-89	1989-90	1990-91	1991-92
Base cost (Rs	3.45	7.95	15.33	26.52	14.42	35.31	65.12	118.62	149.53
Year	1992-93	1993-94	1994-95	1995-96	1996-97	1997-98	1998-99	1999-2000	2000-01
Base cost (Rs	137.76	207.83	186.60	185.05	171.87	134.83	113.96	177.85	64.01

Source: [DAE 2002b].

**Table 4: Capital Costs of Operating Reactors**

Station	Capacity (MW)	Original Cost (Crore)	Revised Cost (Crore)	Criticality Year
TAPS 1 and II	2 x 160	92.99	-	1969
RAPSI	1 x 100 <sup>14</sup>	33.95	73.27	1972
RAPS II	1 x 200	58.16	102.54	1980
MAPSI	1 x 220	61.78	118.83	1983
MAPS II	1 x 220	70.63	127.04	1985
NAPS 1 and II	2 x 220	209.89	745 <sup>15</sup>	1989 and 1991
Kakrapar 1 and II	2 x 220	382.5	1,335	1992 and 1995
Kaiga 1 and II	2 x 220	730.72	2,896	1999 and 2000
RAPS III and IV	2 x 220	711.57	2,511	2000

Sources: [DAE 1996: 67; DAE 2002b],

**Table 5: Expenditure Pattern Assumed for Kaiga III and IV**

---

Year before commissioning	-5	-4	-3	-2	-1	0
Fraction spent (per cent)	1.9	9.7	20.2	30.9	27.3	10

---

Source: [NEA1998].

However, at the end of the economic lifetime of the reactor when the ('leased') HW is returned to the DAE, there is a cash in-flow, which must be discounted to the time of commissioning.

There are practically no public figures available for the amount of HW produced in the DAE's heavy water plants (HWP). The DAE annual performance budgets list, for example, the annual electricity production at various reactors; however, they conspicuously avoid giving any numbers for HW production. In the past, the DAE has claimed that because of its strategic value, it would not disclose the production levels.

What little information is available is suggestive of poor performance. In 1992, *The Times of India* reported that only 273 tonnes of HW were produced in all the HWP put together [Fernandez 1992], implying an average capacity factor of about 50 per cent. The CAG report for 1988 reported that the "Tuticorin [heavy water] plant produced 20.6 per cent of the installed capacity in the last eight years" (i.e., between July 1978 and March 1986). The best production was 42.7 per cent of the design capacity. The plant has "been able to operate on an average for about 150 days...per annum" and "the consumption of spares and maintenance cost was high and Rs 190 lakhs had been spent per annum on an average" [CAG 1988].

The performance of HWPs appears to have improved; in 1998, 100 tonnes of HW were exported to South Korea [Anonymous 1997].<sup>17</sup> In part, this surplus availability of HW is because the expected growth in nuclear power did not take place. Even in recent years, however, a number of plants have had prolonged outages. The Talcher plant, in particular, has been suspended for many years since the associated fertiliser plant has not been operating satisfactorily [DAE 2000: 24-25]. Similarly, during 2002-03 the plant at Tuticorin was affected by frequent outages of the connected fertiliser plant [DAE 2003: 5]. The Thai plant had extended outages in 1998-99, whereas the Hazira and Kota plants had prolonged outages in 1997-98 [DAE 2000: 24; DAE 1999:20]. Consequently in both years, the total target production in HW was not met.

The cost of HW produced in the DAE's plants has been a matter of dispute. For example, in 1983 the AEC quoted a price of Rs 3,875/kg whereas the CAG calculated that it should be Rs 13,800/kg [Reddy 1990]. Since these estimates relied on the earlier plants, and newer plants appear to be performing better, we look at the case of the most recently commissioned HWP at Manuguru.

Sanctioned in 1982, the Manuguru HWP has an annual capacity of 185 metric tonnes (MT) of HW. The estimated cost of the Manuguru HWP when it was sanctioned was Rs 421.60 crore. In 1989, the plant cost was revised to Rs 661.58 crore. The plant finally started production in December 1991 [CAG 1994]. According to the CAG, the "total capital cost including interest during construction and excluding cost of spares came to Rs 983.38 crore and the increase, with reference to the original estimated cost ... was... 133 per cent." When questioned about the cost escalation, DAE stated that "the grounds for sanction of this project was strategic and not commercial".

The DAE's initial estimate of the cost of production was Rs 5,176 per kg of HW (Rs/kgHW). However, due to slippages in the project schedules and consequential delay in commencement of production, the cost of HW worked out to Rs 7,5297 kgHW as of February 1986 [CAG 1994]. This translates to about Rs 24,880/kgHW at 2002 prices, in the same ballpark as the 1983 figure of Rs

6,635/kgHW (Rs 26,960/kgHW when inflated to 2002 prices) cited by the then head of the DAE [Ramanna 1985]. However, in its 1994 report on Manuguru, the CAG pointed out that "Due to further escalation, the cost would have gone up further - the figures for costing after commencement of production in December 1991 were not produced to Audit" (December 1993). There appear to be no further public estimates of the cost of the project. In order to be conservative, we will use the figure of Rs 24,880/kgHW.

One can understand the rather high cost of HW from not only the high capital costs but also the extremely energy intensive nature of the processes involved in producing heavy water. Therefore, over the last few years, the DAE has been trying to implement energy efficiency measures. According to the DAE, during the period 2001 -2002, energy consumption was reduced by about 6 per cent, thereby effecting savings of around Rs 85 crore [Anonymous 2002].<sup>18</sup> Therefore, the total energy consumption bill was Rs 1,416.67 crore. Excluding the Talcher plant where operations have been suspended, the total production capacity of all HW plants at that time was about 490 tonnes per annum. Even assuming an optimistic 80 per cent capacity factor, the energy cost of producing one unit of heavy water is Rs 18,070/ kgHW. Therefore, a total cost of Rs 24,880/kgHW is quite plausible.

When calculating the cost of the initial loading of HW, one small but pertinent detail is that there is usually a period of about six months or more between the reactor becoming critical and starting commercial operations. For example, Kaiga II became critical on September 24, 1999 but started operating commercially only on March 16,2000 [Anonymous 1999b;NPC2004b]. The reactor is loaded with fuel and HW well before criticality. To be conservative, we assume that the total time between loading with HW and uranium, and the reactor producing electricity commercially is six months. Therefore, just as there is a credit for the HW returned at the end of the reactor life, there will be an additional component in the initial capital cost.

### ***Uranium Fuel Inventory***

Another component of expenditure in setting up a nuclear reactor is the initial uranium loading. A 220 MW reactor uses 3,672 fuel assemblies, each containing 15.2 kg of uranium oxide. The cost of each assembly is reported to be Rs 2,50,000 [Subramanian 2002b].<sup>9</sup> This translates to Rs 16,450/kg of uranium fuel. This is comparable to, but less than, the 1983 price of Rs 4,545 per kg of uranium fuel cited by the then head of the DAE, when translated to 2002 rupees [Ramanna 1985].

The NPC obtains its fuel from the Nuclear Fuel Complex. Rather than pay the production costs plus a reasonable rate of return, the fuel is reportedly 'hired' at an administrative price set by the DAE [Wood 1991]. However, the true cost of nuclear electricity must include this cost. A 1985 paper by the DAE suggests that 50 per cent of the cost of initial uranium fuel loading is already included in the capital cost estimates [Srinivasan 1985a]; reprinted in [Srinivasan 1990: 127-37]. Even assuming this to be true, within the DCF methodology we have used, the remaining 50 per cent of the cost has to be included as part of the initial capital costs. Again, because of the assumed six-month period between fuel loading and the commercial delivery of electricity, there is an additional component to the fuel cost.

We will also assume that the nuclear plant stores about 1.5 months worth of uranium (at the assumed capacity factor) and HW (to account for expected losses) and incorporate this as a capital cost.<sup>20</sup>

### ***Decommissioning Costs***

Within the DCF methodology, the cost of decommissioning a reactor, which is done at the end of the economic life of the reactor and a long period of cooling, which we assume to be 40 years, should be incorporated as a capital expense. While there is little experience with actually decommissioning nuclear reactors and how much it costs, agencies that promote nuclear energy typically assume that decommissioning would cost between 9 per cent and 15 per cent of the initial capital cost of a nuclear

power plant [UIC 2001]. There are other estimates. The US Nuclear Regulatory Commission estimates the cost of decommissioning nuclear reactors to be about \$300-450 million [NRC 2004]. Since the typical US nuclear reactor costs about \$1,500/kW and has a capacity of 1,000 MW, this is equivalent to 20-30 per cent of capital costs or \$300-450 per kW. On the higher side, decommissioning the 1,240 MW Superphenix is estimated to cost \$4,000 per kW.

Though based on some limited experience, the numbers cited above are only estimates. Actual experiences have often been significantly more expensive. Decommissioning the 100 MW Niederaibach HW reactor cost \$1,910 per kW while the 45 MW Japan Power Demonstration boiling water reactor cost \$3,180 per kW [WISE 1998].

Nevertheless, in order to be conservative, we will assume that decommissioning expenses are 10 per cent of the initial capital cost. Decommissioning is usually divided into three stages [Saddington 1983]. In rough correspondence with these stages we assume that 40 per cent of the decommissioning expenses occur when the reactor is shutdown at the end of the economic life of the reactor, another 20 per cent at 20 years following shutdown, and the remaining 40 per cent, 40 years after shutdown.

As mentioned earlier, there is no consensus on what the discount rate should be chosen for calculations of economics of electricity generation. This debate is most intense when it comes to costs that are borne by future generations.<sup>21</sup> Choosing a large discount rate would mean that future expenditures are given very little weight in economic calculations. Some economists have proposed that in the interests of intergenerational equity, such activities should be valued at a zero or a very low discount rate [Howarth andNorgaard 1993]. One suggested approach is to use two discount rates, one for the near term expenditures and one for long-term expenditures. For example, the Charpin report on the future of nuclear energy in France chooses a 6 per cent discount rate for expenses in the first 30 years and a 3 per cent discount rate for expenditures thereafter [Charpin et al 2000]. Decommissioning expenses would fall in the latter category. For simplicity and in order to be conservative (i e, favourable to nuclear power), we choose the same discount rate for all expenditures, which, as mentioned earlier, is varied in our calculations.

**Table 6: RAPS-1 Heavy Water Escape and Losses**

Year	Escape (kg/day)	Loss (kg/day)	Annual Loss (Tonnes)
1972	135	31	11.3
1973	197	69	25.2
1974	249	57	20.8
1975	386	77	28.1

Source: Srinivasan 1990, p24.

### **Recurring Costs**

#### ***Fuel Loading Costs***

The amount of fuel needed to produce a unit of electric power is given by the formula:

$$\text{Fuel Used} = \frac{\text{Electrical power generated}}{((\text{thermal efficiency}) \times (\text{burn up}))}$$

The thermal efficiency is the electricity generated per unit thermal power output. The burn up is the heat liberated per unit mass of fuel irradiated; it depends on the reactor type, the fuel used (level of uranium enrichment), and fuelling practices. In the case of the PHWRs we are considering, the average



burn up is 7,000 MWD/tU (megawatt-day per tonne of uranium) [Hibbs 1997a; Changrani et al 1998]. The thermal efficiency for PHWRs is taken to be the design efficiency of 0.29 [Balakrishnan 1999]. In terms of gross generation, the uranium utilisation is 20.5 mg/kWh (milligram per kilowatt-hour).

### ***Heavy Water Make-up Costs***

There are also routine losses of heavy water in PHWRs. This is due to many reasons. For example, during the initial years at the Rajasthan Power Station, there were several failures involving heat exchangers [Ghosh 1996]. These have HW on one side and cooling water on the other. Thus, when they fail, the HW could get mixed with cooling water and escape. There have also been a number of HW leaks and spills - in 1997 alone, such leaks occurred at the Kakrapar I, MAPS II and Narora II reactors [IAEA 1998: 301-20). Such leaks could occur due to various causes. For example, on April 15, 2000, vibration caused the failure of a gasket in the moderator system piping of the Narora II reactor and 7 tonnes of HW leaked out [AERB2001: 13].

Typically some of the HW that is spilt or has otherwise escaped is collected, purified and reused but the rest is discharged into the atmosphere. This creates a radiation hazard to workers and potentially the general public due to the tritium build-up in the HW [Ramana 1999].<sup>22</sup>

In the early years of RAPS-I operations, routine escape and losses were fairly high (Table 6). These have since reduced. In the 1980s, the DAE estimated that the annual HW make-up requirement for two 235 MW reactors (subsequently de-rated to 220 MW) was 16 tonnes/year [Ramanna 1985]. More recently, the first managing director of the NPC states that the annual make-up of HW in a 220 MW reactor is 7 tonnes/year [Kati 2003: 39]. Another report mentions that average HW losses for the Kakrapar reactors were "between 500 and 600 kg/month", or about 6 to 7.2 tonnes per year [Hibbs 1997b]. We will assume that each 220 MW reactor loses 7 tonnes/year.

### ***Operations and Maintenance Cost***

Operating and maintaining a nuclear power plant involves a number of expenses including paying the many trained professionals needed to run the plant, materials for maintenance, site monitoring, operating waste management facilities, collecting and purifying heavy water that escapes, and so on. Once again there is little data available publicly. We will assume that this is 2 per cent of the capital cost.<sup>23</sup>

### ***Waste Management***

The problem of dealing with radioactive nuclear wastes has been one of the most contentious aspects of nuclear power programmes around the world [NEA 1996 and Berkhout 1991]. Since some of these wastes are extremely long lived, the generation of these wastes represents a burden to future generations who do not utilise the electricity produced in these nuclear reactors but may have to undertake measures to ensure that these radioactive materials do not enter their food chain, water resources, and so on. Any attempt at quantifying the costs involved is bound to have enormous uncertainties. Nevertheless, the approach used by nuclear power advocates has been to use the cost of setting up a structure that is expected to contain the radioactive materials within it for a long period of time as the cost of waste management. Despite the controversies involved, we shall follow this approach.

Most of the radioactivity produced is contained in the spent fuel, i e, fuel after irradiation in nuclear reactors. Besides this, large quantities of low-level solid and liquid wastes are also produced during reactor operation and maintenance.<sup>24</sup> These are largely treated on-site and we will assume that the expenses incurred therein are included in the operations and maintenance costs.

Countries around the world have adopted one of two approaches to deal with the highly radioactive spent fuel. In the first, the spent fuel is 'directly disposed' by keeping them first in intermediate storage and eventually storing them in geological repositories. The other approach is to 'reprocess' the spent fuel to extract plutonium and the unused uranium, and concentrate the most highly radioactive components in the spent fuel into liquid 'high level waste'. Though controversies remain, it is generally accepted that direct disposal is the cheaper method of dealing with nuclear wastes at current uranium prices on the international market [Berkhout 1997; NEA 1994; Bunn et al 2003]. At current uranium prices, [Bunn et al 2003] estimate that reprocessing adds "more than an 80 per cent increase in the costs attributable to spent fuel management (after taking account of appropriate credits or charges for recovered plutonium and uranium from reprocessing)" and the difference in costs "is likely to persist for many decades."

The DAE has adopted the more expensive route of reprocessing to deal with spent fuel. The rationale offered for this choice has been the three-stage programme envisioned by the DAE. The first stage involves the use of uranium fuel in PHWRs, the second stage involves fast breeder reactors that use plutonium from reprocessed spent fuel from PHWRs and thorium to produce uranium-233, and the third stage involves reactors using uranium-233 and thorium [Kakodkar 2000]. Since the second stage of the programme requires plutonium, reprocessing is needed to proceed with this programme. This requirement is used by the NPC to neglect the cost of waste disposal from PHWRs. In the NPC's analysis of the economics of PHWRs, "the cost of waste disposal has been assumed to have trade off with the amount of reprocessed fuel generated for next stage of nuclear power programme" [Nema 1999].

Even if one were to follow the NPC's logic and assume that the hugely expensive infrastructure needed for reprocessing is a part of the second stage of the nuclear power programme, there is still the cost involved in dealing with the spent fuel prior to reprocessing. Because the spent fuel as it comes out of the reactor is highly radioactive and produces a lot of heat, it is initially kept under water for cooling. In India, this is done for a minimum of 430 days [Changrani et al 1998]. In practice it may be more, even up to 5 to 10 years, which would increase the waste management costs at the nuclear power plant [Srinivasan 1995]. Then it has to be shipped to the reprocessing plant.<sup>25</sup> Once again because of the high radiation levels (even after cooling), spent fuel shipping containers must be heavily shielded, and must be designed to stringent safety standards. For these reasons the cost of spent fuel shipping is not an insignificant component of the fuel cycle cost [Graves 1979: 261]. The OECD's Nuclear Energy Agency quotes a price of \$13 per kilogram (1991 US dollars) for transporting spent fuel from PHWRs [NEA 1994: 78]. Converting this to 2002 rupees, this is equivalent to Rs 878/kg of spent fuel.

To estimate the cost of waste management, we will assume that the spent fuel is simply handed over to the reprocessing plant and the only cost incurred as part of the fuel cycle of the PHWR is the cost of transportation. This is a very conservative assumption when calculating the electricity price from PHWRs. A fairer evaluation would attribute at least part of the reprocessing expenditures to the electricity generation costs at PHWRs.

### **Performance**

The cost of electricity depends on the efficiency, measured in terms of load factor or capacity factor, with which the generation facility operates. This cost varies inversely as the capacity factor. For long, the DAE's reactors were among the poorest performers in the world. In December 1994 *Nuclear Engineering International*, a standard trade journal, found that the average lifetime load factor for Indian reactors was 36.08 per cent, the lowest among the 18 countries with four or more nuclear reactors; only Brazil, with just one reactor, fared worse [Howles 1995]. Four years later, this position was unchanged with the lifetime average load factor still the lowest [Anonymous 1999c]. However, the performance of the NPC's reactors has been improving over the last few years. This suggests that the NPC is over its teething problems. But it also reflects the recent dramatic increases in funding for the DAE (Table 1). Further, at the level of

individual reactors, performance has remained erratic. For example, in 2002-03, the Kakrapar-I reactor had a record 98 per cent capacity factor, but it decreased to 78 per cent in 2003-04, and has deteriorated further in the 2004-05 [NPC 2004c].

This improved performance of nuclear reactors must be balanced with two factors. First is the fact that similar improvements in performance have also been noted in many other sources of power. The average load factor in thermal power plants, for example, has increased from 54 per cent in 1990-91 to 69.97 per cent in 2001 -02, with plants of capacity greater than 250 MW having an average load factor of over 80 per cent [CEA 2002]. Performance of the plants run by the National Thermal Power Corporation (NTPC) has been significantly better; these increased from 70 per cent in 1992-93 to 84.4 per cent in 2003-04 [NTPC 2004]. The second factor is that with the commissioning of several reactors over the past few years — more than half of the currently installed capacity was commissioned during the 1990s — the average age of the reactor units is low. As these age, one would expect to see a deterioration of performance as well as increased costs to keep them running.

It is instructive, therefore, to look at the average lifetime load factors of the DAE's PHWRs (listed in Table 7). The average of these is 65.1 per cent. To accommodate the possibility of improved performance and to be favourable to nuclear power, we will assume a capacity factor of 80 per cent as the base figure in our calculations. This is much higher than the value of 68.5 per cent (or 70 per cent) commonly assumed in setting tariffs in power purchase agreements. Such a high capacity factor partially offsets the capital-intensive nature of nuclear power.

Another aspect of plant performance is the amount of electricity consumed by the power plant itself. The official in-plant consumption for all electricity-generating plants is 7-8 per cent [NTPC 2004; CSO 1999]. However, looking at actual figures for gross generation and net exports at the DAE's nuclear reactors, the in-plant consumption figures in per cent, are 13.4, 12.4, 11.5, 11.3, 12, 11.7, and 11.9 for each of the years between 1994-95, and 2000-01 respectively [DAE 1997: 10; DAE 1998: 14; DAE 1999: 12; DAE 2000: 13; DAE 2002b: 27]. We will, therefore, assume 12 per cent for the in-plant consumption in the case of the Kaiga reactors.

## **Costs of Coal Power**

For calculating the cost of producing electricity from coal, we chose the case of the Raichur VII Power Station (RTFS VII). Like the Kaiga I & II reactors, RTFS VII is also a relatively recent plant. It has a capacity of 210 MW, roughly the same as each of the Kaiga reactors, and is an example of multiple projects at the same location (just as Kaiga III and IV are co-located with Kaiga I and II). Being in the same geographical region, it feeds into the same grid and therefore faces roughly similar problems from grid instabilities.

The RTFS VII project was sanctioned on March 4, 1999 and the plant was synchronised to the grid on December 10, 2002; till March 2003, the total expenditure came to Rs 491.33 crore [CEA 2004a].<sup>26</sup> This is less than the sum often quoted as the expenditure on the plant because it does not include IDC. The annual expenditures during the four years 1999, 2000, 2001, and 2002 are assumed to be 10 per cent, 40 per cent, 40 per cent, and 10 per cent of the total. As with nuclear plants, we will assume that the plant stores about 1.5 months' supply of coal and furnace oil and incorporate this into the capital cost.

Operation and maintenance expenses at thermal plants are usually set at 2.5 per cent of the capital cost and we will follow that practice [Mahalingam 2001]. Based on actual generation data at the Raichur units [CEA 2002], we use an auxiliary consumption rate of 8.5 per cent. We will assume that the RTFS VII station has an economical lifetime of 30 years (as opposed to 40 years for the Kaiga reactors).

The main expense in producing electricity from thermal power stations is the fuel. The fuel cost depends on the amount of coal used to generate one unit of power. At the other Raichur stations [RTFS I to VI], the coal consumption for 2001 -02 was 0.63 kg/kWh [CEA 2002]. We assume the same consumption rate for RTFS VII.

**Table 7: PHWR Load Factors Until 2003**  
(In per cent)

Station	Cumulative Load Factor
RAPS I	23.31
RAPS II	52.65
MAPSI	52.82
MAPS II	52.92
NAPS I	60.62
NAPS II	67.82
Kakrapar I	70.91
Kakrapar II	84.14
Kaiga I	80.70
Kaiga II	80.91
RAPS III	77.98
RAPS IV	79.20

Source: Power Reactor Information System (PRIS) Database, International Atomic Energy Agency, available on the Internet at <http://www.iaea.org>

The two primary qualities of coal that are of interest to thermal power plants are the calorific (energy) content and the proportion of ash. Inferior grade varieties of coal have lower calorific content and higher ash content. Since the quality of coal used varies from plant to plant and over time, we follow the expert committee on fuels for power generation and assume a standardised coal grade with calorific content of 3,750 kCal/ kg [CEA 2004b]. The basic cost of this grade of coal at the pithead including taxes, duties and royalty is estimated by the expert committee to be Rs 517/tonne; the distance from Raichur to the coal producing regions of Eastern India is about 1200 km and the cost of freight for distances above 1,200 but below 1,500 km is Rs 894.9/tonne [CEA 2004b].<sup>27</sup> Thus, the effective cost of domestic coal at the Raichur plant works out to be about Rs 1,412/tonne.

The corresponding cost for imported coal with calorific content of 5,400 kCal/kg at the port is about Rs 1,925/tonne; the distance from Raichur to Mangalore port is about 450 km and the cost of freight for distances between 300 and 500 km is Rs 25 I/tonne. Thus the effective cost of imported coal at the Raichur plant works out to about Rs 2,175/tonne. With these figures, the levelised cost of electricity using imported coal is about Rs 0.03/kWh higher than when using domestic coal. Thermal plants also use furnace oil, whose consumption at the Raichur plant is about 2 ml/kWh. Its price is about Rs 18/litre [NTPC 2005].

All these prices are, of course, subject to market fluctuations and standard inflationary increases. In principle, the price of uranium would also be subject to similar changes.<sup>28</sup> We will ignore the fluctuations since these should get averaged over the long lifetime of the plant. The inflationary increases are implicitly taken into consideration by working in fixed-year Rupees.

Just as we included the cost of waste disposal in the case of nuclear power, here we include the cost of disposal of ash. Typical ash content in Indian coal is about 40 per cent, of which about 80 per cent is fly ash and the balance 20 per cent is bottom ash [CPCB 2000]. In 1999, the ministry of environment and

forests stipulated that all coal thermal power plants should utilise the fly ash generated for manufacturing bricks, road laying, making embankments, in landfills, and so on. The same notification also ordered brick manufacturers, public works departments, the National Highway Authority, and other agencies to use ash generated in coal plants. The ash is, at least initially, to be provided free of cost. However, there are definite savings for the end users in terms of reduced requirements for various inputs.<sup>29</sup>

In the case of the Raichur thermal plant, the fly ash generated is used for the manufacture of portland pozzolona cement (PPC) by the Associated Cement Companies, which has exclusive rights to collect fly ash for free from three of the seven plants at that site [Giriprakash 2001]. The use of fly ash for PPC manufacture lowers the costs of cement production due to reduced requirements for thermal and electrical energy, and lower consumption of clinker. Therefore in general PPC manufacturers have been willing to pay the costs of transporting the fly ash from thermal plants [Shah 1999]. In some cases, they have even been willing to purchase the fly ash.

Both fly ash and bottom ash can be used to manufacture bricks, in landfills, and to build roads and embankments. The cost of using fly ash for brick manufacture have been estimated [Bhattacharjee and Kandpal 2002a]. Using these numbers, and assuming the same figures for the case of bottom ash as well, we estimate an ash disposal cost of not more than Rs 174/tonne.

At Rs 174 per tonne of ash, the disposal cost for coal with 40 per cent ash content is Rs 0.05/kWh. It should be emphasised that this is costlier than current practice because it assumes that the power plant bears part of the cost for a more environmentally benign way of disposing waste. This is also more expensive than using the ash for cement manufacture. However, in order to be conservative, i e, favourable to nuclear power, we use this figure.

In line with the current government policy, we have not imputed any economic costs for the air pollution resulting from coal-based thermal plants. Though such pollution has gained in policy relevance with the heightened concern about global warming, inclusion of pollution costs remains problematic for many reasons, especially in the context of a comparison with nuclear power. This is because the pollution externalities for nuclear power are difficult to quantify for many reasons. Two proximate ones are the scientific and political controversies surrounding the health impacts of low level radiation and the lack of reliable data on radioactive emissions from nuclear facilities and the impossibility of independent verification of the scarce data available in the Indian context [Ramana and Gadekar 2003]. Finally, unlike carbon dioxide, which has substantial sinks in the terrestrial and marine ecosystems, there is no way to render radioactive materials benign. Hence, the environmental and public health impacts of long-lived radioactive wastes could occur well into the future, possibly tens of thousands of years from now. There are inherent problems with quantifying these. Thus, it is all but impossible to make a fair comparison of environmental externalities between coal power and nuclear power.

## **Results and Comparison**

We now compare the costs of nuclear power from the Kaiga I/II and Kaiga III/TV reactors and cost of thermal electricity from RTFS VII using domestic coal. Table 9 summarises the figures used in our calculations.

As mentioned earlier, the cost of electricity is calculated as a function of discount rate. We begin with the comparison for a (real) discount rate of 1 per cent. As seen in Table 10, the levelised cost of electricity from nuclear reactors is lower than the case of RTFS VII (using domestic coal). The cost of nuclear power is dominated by the capacity cost whereas that of thermal power is dominated by the fuel cost.

Since only the capacity cost varies with discount rate, for other values of the discount rate we only list the total levelised cost. These are listed in Table 11. The last row lists levelised costs for a real discount rate of 6 per cent, which, as mentioned earlier, roughly corresponds to the discount rate assumed by the Planning Commission and the Central Electric Authority.

**Table 8: Cost of Making Fly Ash Bricks**

	Percentage I	Percentage II
Fly ash bricks cost differential (Rs per 1000 bricks)	100	100
Volume per brick (cm <sup>3</sup> )	1795.4	1795.4
Density of brick (kg/m <sup>3</sup> )	1770	1770
Mass of 1000 bricks (kg)	3177.8	3177.8
Fly ash utilisation in fly ash clay brick	0.25	0.25
Fly ash utilisation in fly ash sand lime brick	0.6	0.6
Percentage of fly ash clay bricks as fraction of total fly ash based bricks (assumed)	50	30
Percentage of fly ash sand lime brick (assumed)	50	70
Fly ash used in 1 000 fly ash based bricks (tonnes)	1.35	1.57
Cost of fly ash utilisation (Rs/tonne-flyash)	74.0	63.6
Transportation cost (Rs/km/tonne)	2	2
Assumed distance of transport to brick kiln (km)	50	50
Cost of fly ash utilisation including transport costs (Rs/tonne)	174	163.6

**Table 9: Figures Used in Calculations**

	Kaiga	Kaiga	RTPS
	I and II	III and IV	VII (D)
Sum of annual construction costs <sup>30</sup> (Rs crore)	1,816	2,866.88	491.3
Power plant capacity (MW)	440	440	210
In-plant consumption (per cent)	12	12	8.5
Economic lifetime (years)	40	40	30
Uranium fuel price (Rs/kg)	16,450	16,450	
Initial uranium loading (tonnes)	111.6	111.6	
Fraction of initial fuel cost included in Capital Cost	0.5	0.5	
Assumed burn-up (MWD/tU)	7,000	7,000	
Uranium utilisation (kg/kWh (gross))	2.05E-05	2.05E-05	
Heavy water price (Rs/kg)	24,880.00	24,880.00	
Initial heavy water loading (tonnes)	420	420	
Heavy water losses (kg/year)	14,000	14,000	
Transport of spent fuel (Rs/kg)	878	878	
Decommissioning cost (fraction of capital cost) (percent)	10	10	
Coal cost (Rs/tonne)			1,412
Coal calorific content (kCal/kg)			3,750
Coal Consumption (kg/kWh)			0.63
Coal ash fraction (per cent)			40
Ash disposal cost (Rs/tonne)			174
Furnace oil consumption (ml/kWh)			2
Furnace oil cost (Rs/litre)			18
O and M cost (fraction of capital cost) (per cent)	2	2	2.5

**Table 10: Levelised Costs (in Rs/kWh) of Different Options for Discount Rate of 1 Per Cent, Capacity Factor of 80 Per Cent, Economic Lifetime of 40 Years for Nuclear Reactors, 30 Years for Thermal Plant**

	Kaiga I and II	Kaiga III and IV	RTPS VII (D)
Capacity cost (including O&M) Rs/kWh	0.65	0.67	0.27
Heavy water make-up cost (Rs/net kWh)	0.13	0.13	0
Fuel cost (Rs/net kWh)	0.38	0.38	1.01
Waste disposal cost (Rs/net kWh)	0.02	0.02	0.05
Total levelised cost (Rs/kWh)	1.18	1.20	1.33

**Table 11: Total Levelised Costs (in Rs/kWh) of Different Options for Different Discount Rates, Capacity Factor of 80 Per Cent, Economic Lifetime of 40 years for Reactors, 30 Years for Thermal Plant**

Discount Rate (Per Cent)	Kaiga I and II	Kaiga III and IV	RTPS VII (D)
2	1.32	1.32	1.36
2.5	1.39	1.39	1.37
3	1.48	1.46	1.39
4	1.66	1.62	1.42
5	1.87	1.79	1.45
6	2.10	1.98	1.49

The exact value of the discount rate (i.e., the crossover point) at which the cost of thermal power becomes cheaper than nuclear power from Kaiga I and II stations is about 2.33 per cent (levelised cost of Rs 1.366). While there is debate on the appropriate discount rate for public investments, few would argue that 2.33 per cent is a high rate for long-term investments, especially in a country with multiple demands for capital. The crossover point determined by Reddy (1990) varied from 5 to 7.5 per cent (nominal discount rate).

As mentioned earlier, the utilisation of a power plant (expressed through the capacity factor) is a determinant of the price of electricity generated. Since nuclear power is capital intensive, lower capacity factors would reduce its competitiveness. This is demonstrated in Table 12 that lists the crossover point in discount rates for three different capacity factors. If the capacity factor is only 75 per cent, then nuclear power is cheaper than coal power only for discount rates lower than 1.7 per cent.

The crossover point also varies with the assumed lifetimes of the power plants. If one were to assume that the economic lifetime of the coal plant is the same as that of the nuclear plant, i.e., 40 years, the crossover point (at 80 per cent capacity factor) between Kaiga III and IV and RTFS VII becomes 2.01 per cent, and that between Kaiga I and II and RTFS VII becomes 2.06 per cent. As mentioned earlier, all of these crossover points are un-realistically low values. Therefore, for realistic values of discount rates, nuclear power from the Kaiga reactors is more expensive than electricity generated in RTFS VII.

## Conclusions

Our primary goal in this paper was to calculate in detail, dealing exhaustively with many of the sub-processes involved and using updated data, the cost of producing electricity from the DAE's pressurised heavy water reactors. We have done so in a transparent manner laying out the methodology and assumptions explicitly. This allows for the possibility that it can be corrected, should better data become available; given the limited amount of data publicly available, this is quite likely.

Our analysis demonstrates that electricity from PHWRs is more expensive for real discount rates above about 2-3 per cent, under most reasonable assumptions. Such rates may not be realistic over the decades that these plants are to operate.

One criticism of this study is that we have considered nuclear plants of smaller capacities, namely, 220 MW, even though it is expected that electricity from larger capacity nuclear plants would be cheaper. And therefore, the argument goes, if one were to compare such larger sized plants, then electricity from nuclear reactors would be cheaper than electricity from similar sized coal based thermal power plants. There are two problems with this argument. First, the experience of the last five decades of nuclear power suggests that early predictions of costs are frequently wrong. This is especially true in the case of the DAE. In all the reactors constructed so far, final cost figures have been higher than originally estimated.<sup>31</sup> Thus, without experience with actually constructed reactors at lower prices, any claims about their cost should be viewed with some scepticism.

**Table 12: Variation with Capacity Factor**  
(*In per cent*)

Capacity factor	75	80	85
Crossover point between Kaiga I and II and RTFS VII (D)	2.0	2.33	2.65
Crossover point between Kaiga III and IV and RTFS VII (D)	1.93	2.33	2.7

Second, a fair comparison would also include the effects of cost-cutting measures at coal based thermal plants, including both capital cost reductions and fuel cost reductions.<sup>32</sup> In this regard, RTPS-7 can be counted as an example of a plant that has reduced capital costs and construction times successfully. However, this reduced capital cost does not make the comparison of Kaiga nuclear plants with RTPS-7 an unfair one because its distance from coal mines is somewhat large, thereby increasing its fuel costs, which dominate the cost of producing electricity at thermal plants.

Considering that electricity from the 220 MW Kaiga plants is costlier than thermal power for a large range of parameters, the conclusion that nuclear power is more expensive than thermal power from coal is robust. This contradicts numerous claims by the DAE that nuclear power is cheaper than coal based thermal power at sites which are 800-1,000 km away from coal mines. Nuclear power plants, therefore, have been and remain a costlier way of trying to address India's electricity needs than coal based thermal plants.

Email: ramana@isec.ac.in



## Notes

[MVR would like to thank Eric Larson, Indira Rajaraman, D Narasimha Rao, Navjot Singh, Suchitra J Y, Frank von Hippel, and Sharad Lele and other colleagues at the Centre for Interdisciplinary Studies in Environment and Development for useful discussions, probing questions, and critical comments. We thank the anonymous reviewer for useful inputs.]

- 1 Two 540 MW reactors are due to become commercial soon raising the total nuclear capacity to 3,850 MW.
- 2 The summary of this study was published as [Nema 1999]. When asked for a copy of the full study, the NPC's spokesperson told one of the authors (MVR) that it was not available to the public.
- 3 For comparison, the final (revised) budget for the Ministry of Non-Conventional Energy Sources that is in charge of developing solar, wind, small hydro and biomass based power in 2002-03 was Rs 473.56 crore. These sources between them comprise 4,800 MW of generating capacity (MNES, 2004), as compared to the 2,770 MW of nuclear power. Their contribution to actual electricity generation would, of course, be smaller because these are intermittent sources of power.
- 4 Pressurised Heavy Water Reactors use heavy water (in which the hydrogen atoms are replaced by deuterium, a heavier isotope of hydrogen).
- 5 This compares the economics of generating electricity from two different sources of power. Transmission and distribution costs are external to the production process itself and their inclusion would make the comparison dependent on the locations of the power plant and the load centres.
- 6 Even ignoring the time value of money, this is inconsistent because it adds rupees from different years without considering differences in purchasing power due to inflation.
- 7 The discount rate used here can be either a nominal discount rate  $d_n$  or a real (i.e., inflation corrected) discount rate  $d_r$ , with the two options being related as:  $d_r = (d_n - i)/(1 + i)$  or approximately  $d_r = (d_n - i)$ , subject to an error of  $1/(1 + i)$ . If inflation has already been taken into account (for example when prices for one year are adjusted for another year using inflation rates), then the discount rate is a real discount rate.
- 8 The data is available on the internet to subscribers at <http://www.worldbank.org/>
- 9 In other words, the comparison is for an investor who already has the required funds.
- 10 The DAE typically constructs two nuclear reactors at one time at each site. This is why we treat the two reactors as one unit.
- 11 A nuclear plant is said to become critical when it starts sustaining a chain reaction. There is usually a period reserved for safety checks and other operational matters before the reactor actually starts supplying electricity to the grid.
- 12 This is in mixed year rupees, and cannot be directly compared with future reactors whose costs are given in present day rupees.
- 13 The collapse is usually termed "delamination" in official documents [Mohan 1994]. There was also a less publicised fire on the same dome [Anonymous 1999a].
- 14 This was derated from 200 MW.
- 15 The revised cost estimates for NAPS, Kakrapar and Kaiga includes interest during construction.
- 16 For nuclear power cost increases in the case of the US, see Komanoff 1981.
- 17 From the reported value of 20 million dollars for the 100 tonnes of heavy water exported, it would seem that that the heavy water was probably sold below cost of production.
- 18 Elsewhere the savings have been quoted as being Rs 100 crore [Anonymous 2001].
- 19 The article itself mentions a price of "about Rs 25 lakh" for a fuel assembly. However, this appears to be a misprint or an error. When asked for clarification, the author confirmed that the engineers at the Nuclear Fuel Complex had actually mentioned a price of Rs 2.5 lakh [Subramanian 2002a].
- 20 This is sometimes called working capital.
- 21 See the discussion in Bunn et al 2003.
- 22 In the case of the leak at Narora-II on April 15, 2000, one worker received an internal dose of 47.12 mSv, well in excess of the 30 mSv annual limit on radiation doses to workers.

- 23 We thank the anonymous reviewer for suggesting this.
- 24 For an estimate of the quantities involved see Ramana et al 2001.
- 25 Like most of the DAE's nuclearpower stations, the Kaiga nuclear reactors do not have a reprocessing plant on-site. Therefore, if its spent fuel is to be reprocessed, it must be shipped to either Tarapur or Kalpakkam.
- 26 Expenses after that are considered part of O&M expenses.
- 27 We are being somewhat unfavourable to the cost of coal power since the kind of inferior grade coal that we have assumed for RTFS is available from points closer to Raichur.
- 28 In the case of uranium, however, one would expect to see an increase in the price over and above inflation in the not-too-distant future because of diminishing domestic reserves. We ignore this increase in order to be conservative.
- 29 For an estimate see Bhattacharjee and Kandpal 2002b.
- 30 This is the sum of the actual expenditures incurred (or projected to be incurred, in the case of the Kaiga III and IV) and does not include interest during construction (IDC).
- 31 Even in the case of the 540 MW reactors coming up at Tarapur, the initial cost estimate was only Rs 2,427.51 crore. The final cost estimate is of the order of Rs 6,000 crore.
- 32 One way to lower fuel costs would be through coal washing, which decreases ash content, which in turn reduces transportation costs and increases plant efficiencies.

### References

AERB (2001): 'Annual Report 2000-2001', Atomic Energy Regulatory Board, Mumbai.

Anonymous (1997): 'India to Export Heavy Water to S Korea', *Business Line*, November 1.

— (1999a): 'Fire Breaks Out in Kaiga Plant Dome', *The Times of India*, November 13.

— (1999b): 'Kaiga Goes Critical, to Generate Power from January 2000', *The Times of India*, September 25.

— (1999c): 'Load Factors to End September 1998', *Nuclear Engineering International*, March, pp 22-25.

— (2001): 'India: Three-pronged Strategy for Enhancing N-power', *The Hindu*, April 26.

— (2002): 'Heavy Water Board Performs Exceedingly Well', *Nuclear India*, July-August, p 11.

Balakrishnan, Kamala (1999): 'Alternate Fuel Cycles in the Indian PHWR', *BARC Newsletter*, April.

Berkhout, Frans (1991): *Radioactive Waste: Politics and Technology*, Routledge, London.

-(1997): 'The Economics of Reprocessing', *Energy and Security*, October 2.

Bhabha, Homi J and N B Prasad (1958): 'A Study of the Contribution of Atomic Energy to a Power Programme in India' in *Proceedings of the Second United Nations International Conference on the Peaceful Uses of Atomic Energy*, Geneva, pp 89-101.

Bhattacharjee, Ujjwal and TaraChadra Kandpal (2002a): 'Financial Evaluation of Coal Thermal Power Generation Costs in India: Effect of Incremental Costs of Fly Ash Utilisation' in *Proceedings of the World Renewable Energy Congress VII*.

-(2002b): 'Potential of Fly Ash Utilisation in India', *Energy*, 27, pp 151-66.

Bhoje, S B (2001): 'Atomic Energy Obvious Choice for India: Interview with S B Bhoje, Director, IGCAR', *Frontline*, March 30, pp 84-85.

Bose, Deb Kumar (2000): 'Nuclear Power for Eastern India: No Basis for Choice', *Economic and Political Weekly*, September 23, pp 3480-84.

Brealey, Richard A and Stewart C Myers (2000): *Principles of Corporate Finance*, 6 ed, Irwin McGraw-Hill, Boston.

Bunn, Matthew, Steve Fetter, John P Holdren and Bob van derZwaan (2003): 'The Economics of Reprocessing vs Direct Disposal of Spent Nuclear Fuel', Project on Managing the Atom, Harvard University, Cambridge.

CAG (1988): 'Report by the Comptroller and Auditor General of India', Comptroller and Auditor General, New Delhi.

- (1994): 'Report by the Comptroller and Auditor General of India', Comptroller and Auditor General of India.

CEA (2002): 'Performance Review of Thermal Power Stations 2001-02', Central Electricity Authority, <http://www.cea.nic.in/opm/anu0102/31index.pdf>, accessed on November 16, 2004.

- (2003): 'All India Electricity Statistics, General Review 2002-03', Central Electric Authority, [http://www.cea.nic.in/ge\\_re/2002-03/genrev45-61.pdf](http://www.cea.nic.in/ge_re/2002-03/genrev45-61.pdf), accessed on March 4, 2005.

- (2004a): 'Broad Status of Thermal Power Projects in Karnataka', Central Electric Authority, [http://www.cea.nic.in/data/opt2\\_const\\_mon\\_th\\_index.htm](http://www.cea.nic.in/data/opt2_const_mon_th_index.htm), accessed on November 16, 2004.

- (2004b): 'Report of the Expert Committee on Fuels for Power Generation', Central Electric Authority, Planning Wing, New Delhi, also available at [http://www.cea.nic.in/Rep\\_fuels\\_gen.pdf](http://www.cea.nic.in/Rep_fuels_gen.pdf).

Changrani, R D, D D Bajpai and S S Kodilkar (1998): 'Storage of Spent Fuel from Power Reactor in India: Management and Experience' in *Proceedings of the Storage of Spent Fuel from Power Reactors*, pp 65-72, International Atomic Energy Agency, Vienna.

Charpin, Jean-Michel, Benjamin Dessus and Rene Pellat (2000): 'Economic Forecast Study of the Nuclear Power Option', Office of the Prime Minister, Paris, also available at [http://fire.pppl.gov/eu\\_fr\\_fission\\_plan.pdf](http://fire.pppl.gov/eu_fr_fission_plan.pdf).

Chidambaram, R (2001): 'Nuclear Energy Needs and Proliferation Misconceptions', *Current Science*, July 10, 81(1), pp 17-21.

CPCB(2000): 'Benefits of Beneficiated Coal in Coal Based Power Generation in India', Central Pollution Control Board, <http://www.cleantechindia.com/bishtml/210301.18.htm>, accessed on November 16, 2004.

CSO (1999): *Statistical Abstract: India, 1998*, Central Statistical Organisation, Department of Statistics and Programme Implementation, New Delhi.

DAE (1991): 'Annual Report 1990-1991', Department of Atomic Energy, Mumbai.

- (1996): 'Performance Budget 1995-96', Department of Atomic Energy, Mumbai.

- (1997): 'Performance Budget 1996-97', Department of Atomic Energy, Mumbai.

- (1998): 'Performance Budget 1997-98', Department of Atomic Energy, Mumbai.

- (1999): 'Performance Budget 1998-99', Department of Atomic Energy, Mumbai.

- (2000): 'Performance Budget 1999-2000', Department of Atomic Energy, Mumbai.

- (2002a): 'Nuclear Power Generation: Targets and Achievements, 25th Report Presented to the Lok Sabha', Department of Atomic Energy/Lok Sabha Secretariat, New Delhi, also available at <http://164.100.24.208/ls/committeeR/Energy/25th.pdf>.

- (2002b): 'Performance Budget 2001-2002', Department of Atomic Energy, Mumbai.

- (2003): 'Annual Report 2002-2003', Department of Atomic Energy, Mumbai.

- Fernandez, Clarence (1992): 'Heavy Going for Heavy Water Board', *The Times of India*, March 25, p 7.
- Ghosh, G (1996): 'Operational Experiences: Nuclear Power Stations', *Electrical India*, August 15, pp 29-33.
- Giriprakash, K (2001): 'ACC's New Cement Plant at Wadi Commissioned in Record Time', *The Indian Concrete Journal*, May: 307-310.
- Graves, Harvey W, Jr(1979): *Nuclear Fuel Management*, John Wiley, New York and Santa Barbara.
- Hibbs, Mark (1997a): 'First Separation Line at Kalpakkam Slated to Begin Operations Next Year', *Nuclear Fuel*, December 1, pp 8.
- (1997b): 'NPC says Kakrapar Peer Review Should Dispel Foreign Safety Fear', *Nucleonics Week*, December 4, 38(49), pp 8.
- Howarth, Richard and Richard Norgaard (1993): 'Intergenerational Transfers and the Social Discount Rate', *Environmental and Resource Economics*,3, pp 337-58.
- Howles, Laurie (1995): 'Load Factors: 1994 Annual Review', *NuclearEngineering International*, April, pp 26-30.
- IAEA (1998): 'Operating Experience with Nuclear Power Stations in Member States in 1997', International Atomic Energy Agency, Vienna.
- Joseph, Anto (1999): 'India Plans to be Nuke Powerhouse by 2020, Sets a 20,000 MW Target', *The Economic Times*, September 16.
- Kakodkar, Anil (2000): 'Neutron Bomb Capability Exists: Interview with Anil Kakodkar', *Frontline*, December 22, pp 89-91.
- Kati, S L (2003): 'Conceptual Design of Heavy Water Moderated Organic Cooled Reactor', *Nu-Power*, 17(4), pp 36-39.
- Koman off, Charles (1981): *Power Plant Cost Escalation: Nuclear and CoalCapital Costs, Regulation and Economics*, Komanoff Energy Associates,New York.
- Lal, M M (2002): 'Slashing Construction Times and Pre-project Activities in Indian Nuclear Power Projects' in *Proceedings of the 13th AnnualConference of the Indian Nuclear Society (INSAC 2002)*, INS AC, Mumbai.
- Mahalingam, Sudha (2001): 'A Worrisome Tariff Order', *Frontline*,February 2.
- MNES (2004): 'Annual Report 2003-2004', Ministry of Non-Conventional Energy Sources, Delhi, also available at [http://mnes.nic.in/annualreport/2003\\_2004\\_English/index.html](http://mnes.nic.in/annualreport/2003_2004_English/index.html).
- Mohan, M Madan (1994): 'Kaiga Questions: A Gaping Hole in Safety Standards', *Frontline*, June 17, pp 84-85.
- Muralidharan, Sukumar (1988): 'Birth of Nuclear Power Corporation', *Economic and Political Weekly*, January 30, pp 190-92.

NEA (1994): 'The Economics of the Nuclear Fuel Cycle', Nuclear Energy Agency, OECD, Paris.

- (1996): 'Radioactive Waste Management in Perspective', Nuclear Energy Agency, OECD, Paris.

-(1998): 'Projected Costs of Generating Electricity: Update 1998', Nuclear Energy Agency, OECD, Paris.

NEI (1994): 'Power Reactors: Main Data for Individual Units', *World Nuclear Industry Handbook*, pp 71-94.

Nema, A K (1999): 'Nuclear Generation Cost in India', *Nu-Power*, 13(1).

NPC (2004a): 'Kaiga Atomic Power Project 3 &4', Nuclear Power Corporation, <http://www.npcil.org/kapp3&4.asp>, accessed on November 16.

- (2004b): 'Kaiga Atomic Power Station', Nuclear Power Corporation, <http://www.npcil.org/kaigaaps.asp>, accessed on November 16.

- (2004c): 'Kakrapar Atomic Power Station', Nuclear Power Corporation, <http://www.npcil.org/kaps.asp>, accessed on November 16.

NRC (2004): 'Reactor Decommissioning Funding', US Nuclear Regulatory Commission, <http://www.nrc.gov/reactors/decommissioning/funding.html>, accessed on November 16.

NTPC (2004): 'Power Plant Operations', National Thermal Power Corporation, <http://www.ntpc.co.in/operations/operations.shtml>, accessed on November 16.

- (2005): 'Ramagundam Super Thermal Power Station - Stage 111 (500 MW): Tariff Petition for the Period 01.03.2005 to 31.03.2009', National Thermal Power Corporation, <http://www.ntpc.co.in/bidsnotices/docs/Ramagundam.pdf>, accessed on March 9.

Ramana, M V (1999): 'Disturbing Questions', *Frontline*, June 4, pp 119-20.

Ramana, M V and Surendra Gadekar (2003): 'The Price We Pay: Environmental and Health Impacts of Nuclear Weapons Production and Testing' in M V Ramana and C Rammanohar Reddy, (eds), *Prisoners of the Nuclear Dream*, Orient Longman, New Delhi.

Ramana, M V, Dennis George Thomas and Susy Varughese (2001): 'Estimating Nuclear Waste Production in India', *Current Science*, December 10, 81(11), pp 1458-62.

Ramanna, Raja (1985): 'Can Nuclear Energy Claim to be the Only Source of Power in the Future?' C C Desai Memorial Lecture, Administrative Staff College of India, March 4.

Reddy, Amulya Kumar N (1990): 'Nuclear Power: Is It Necessary or Economical?', *Seminar*, June, (1), pp 18-26.

Reddy, Amulya Kumar N, Gladys D Sumithra, P Balachandra and Antonette d'Sa(1990): 'Comparative Costs of Electricity Conservation, Centralised and Decentralised Electricity Generation', *Economic and Political Weekly*, June 2, 35(22).

Saddington, K(1983): 'Decommissioning of Nuclear Facilities' in W Marshall (ed), *Nuclear Power Technology*, Clarendon Press, Oxford, pp 335-67.

Shah, S N (1999): 'Prism Cement Pins Hopes on Higher Net Cement Realisation', *Financial Express*, October 22.

- Srinivasan, M R (1985a): 'Economic Case for Small and Medium Power Reactors in India' in *Proceedings of the International Atomic Energy Agency General Conference*, International Atomic Energy Agency, Vienna.
- (1985b): 'The Indian Nuclear Power Programme' in *Proceedings of the Indo-French Seminar on Nuclear Energy*, pp 9-21, Department of Atomic Energy, Bombay.
- Srinivasan, M R (ed) (1990): *Selected Lectures of Dr M R Srinivasan*, Department of Atomic Energy, Bombay.
- Srinivasan, V S (1995): 'Design, Planning and Siting of Spent Fuel Storage Facilities in India' in *Proceedings of an International Symposium on Safety and Engineering Aspects of Spent Fuel Storage*, International Atomic Energy Agency, Vienna, pp 57-69.
- Subramanian, T S (2002a): Email Communication, June 11.
- (2002b): 'Fuelling Power', *Frontline*, March 29.
- UIC (2001): 'The Economics of Nuclear Power', Nuclear Issues Briefing Paper no 8, Uranium Information Centre, Sydney, also available at <http://www.uic.com.au>.
- WISE (1998): 'Problems of Decommissioning Nuclear Facilities',
- WISE News Communique*, January 23, p 485.
- Wood, Janet (1991): 'Can Nuclear Pay Its Way in India?', *Nuclear Engineering International*, December, pp 52-53.

